


Project X and the Neutrino Factory

Steve Holmes


IDS-NF Meeting
June 11, 2008

Strategic Context

Fermilab Long Range Plan



- Fermilab is the sole remaining U.S. laboratory providing facilities in support of accelerator-based Elementary Particle Physics.
- The Fermilab long-term plan incorporates three strategic directions:



Neutrino Program Evolution

World View



- Long term physics goals:
 - Measure neutrino mass hierarchy
 - Measure complete neutrino mixing matrix, including CP-violating phase, δ
- How?
 - $\sin^2 2\theta_{13}$ to 0.1 $\rightarrow$ 0.01: Double Chooz $\rightarrow$ Daya Bay/T2K/NOvA
 - Mass hierarchy for $\sin^2 2\theta_{13}$ to 0.02: NOvA + T2K
 - $\sin^2 2\theta_{13}$ to 0.001: Project X/DUSEL
 - CP-violation for $\sin^2 2\theta_{13}$ to few $\times$ 0.001: Project X/DUSEL
 - $\sin^2 2\theta_{13}$ less than 0.001: NuFACT


Neutrino Program Evolution

P5 Recommendations




- Intensity Frontier
 - The panel recommends a world-class neutrino program as a core component of the US program, with the long-term vision of a large detector in the proposed DUSEL and a high-intensity neutrino source at Fermilab.
 - The panel recommends an R&D program in the immediate future to design a multi-megawatt proton source at Fermilab and a neutrino beamline to DUSEL...
 - A neutrino program with a multi-megawatt proton source would be a stepping stone toward a future neutrino source, such as a neutrino factory based on a muon storage ring... This in turn could position the US program to develop a muon collider as a long-term means to return to the energy frontier in the US.

Project X Facility Overview





Project X is a high intensity proton facility aimed at supporting a world leading program in neutrinos and rare decays.

NO_vA initially,
DUSEL later




Project X Facility Overview

Provisional Siting



DATE: 11/11/08 BY: S. HOLMES

REV	DATE	DESCRIPTION	BY	DATE




FERMI NATIONAL ACCELERATOR LABORATORY	
L-0 UPSTREAM SERVICE BUILDING	
LINAC PROTON DRIVER	
SITE PLAN	
DRAWING: 4-2-1	CD-0
1	REV.

04 MAR 2005

Project X Facility Overview

High Level Performance Goals



Linac

Particle Type	H ⁻	
Beam Kinetic Energy	8.0	GeV
Particles per pulse	5.6×10^{13}	
Pulse rate	5	Hz
Beam Power	360	kW

Recycler


Particle Type	protons	
Beam Kinetic Energy	8.0	GeV
Cycle time	1.4	sec
Particles per cycle to MI	1.7×10^{14}	
Particles per cycle to 8 GeV program	2.2×10^{14}	
Beam Power to 8 GeV program	206	kW

Main Injector

Beam Kinetic Energy (maximum)	120	GeV
Cycle time	1.4	sec
Particles per cycle	1.7×10^{14}	
Beam Power at 120 GeV	2300	kW


Project X Facility Overview

Scope




- The Project X Facility scope includes:
 - A new 8 GeV, superconducting, H^- linac;
 - A new beamline for transport of 8 GeV H^- from the linac to the Recycler Ring;
 - Modifications to the Recycler required for 8 GeV H^- injection, accumulation, and delivery of protons to the Main Injector;
 - Modifications to existing beamlines to support transfer of 8 GeV protons from the Recycler to the Main Injector;
 - Modifications to the Main Injector to support acceleration and extraction of high intensity proton beams over the range 60-120 GeV;
 - Modifications to the NuMI facility to support operations at 2 MW beam power;
 - Modifications to the Recycler to support a new extraction system that will allow delivery of 8 GeV protons in support of a dedicated flavor program.
-

Project X RD&D Plan



- The goal of the RD&D program is to provide support for Critical Decision 2 (CD-2) in 2011, leading to 2012 construction start.
 - Design and technical component development;
 - Fully developed baseline scope, cost estimate, and schedule;
 - Formation of a multi-institutional collaboration capable of executing both the R&D plan and the follow-on construction project.
- The primary technical goal is a complete facility design that meets the needs of the US research program, as established via CD-0.
 - 2 MW of beam power over the range 60 – 120 GeV,
 - Simultaneous with at least 100 kW of beam power at 8 GeV
 - Compatibility with future upgrades to >2 MW at 8 GeV

Project X RD&D Plan Strategy



- Working backwards (potential delay if/when FY2009 CR):
 - FY12: CD-3 – Start Construction
 - FY11: CD-2 – Establish Baseline
 - FY10: CD-1 – Establish Baseline Range
 - Requires a complete Conceptual Design Report
 - FY09 (spring): CD-0
 - Requires new cost (range) estimate which will be reviewed by DOE
- FY2008 Goals
 - Establish basic performance parameters
 - Develop design concept sufficient to form basis of a cost estimate
 - Understand how/if the linac could support a 2+ MW upgrade
 - Form Project X RD&D Collaboration and establish work assignments for FY09

Project X

360 kW 8GeV Linac

20 Klystrons (2 types)
436 SC Cavities
56 Cryomodules


Front End Linac

325 MHz 0-10 MeV

1 Klystron (JPARC 2.5 MW)
16 RT Cavities


325 MHz 10-120 MeV

1 Klystron (JPARC 2.5 MW)
51 Single Spoke Resonators
5 Cryomodules



325 MHz 0.12-0.42 GeV

3 Klystrons (JPARC 2.5 MW)
42 Triple Spoke Resonators
7 Cryomodules





1300 MHz 0.42-1.2 GeV

2 Klystrons (ILC 10 MW MBK)
56 Squeezed Cavities ($\beta=0.81$)
7 Cryomodules (8 cav., 4 quads)

1300 MHz 1.2-8.0 GeV

13 Klystrons (ILC 10 MW MBK)
287 ILC-identical Cavities
37 ILC-like Cryomodules


ILC LINAC



8 Cavities-1 quad / Cryomodule

Project X RD&D Plan


Relationship to Other Programs: ILC/SRF



- Project X design concept aligns beam parameters with ILC:
 - $9 \text{ mA} \times 1 \text{ msec} \times 5 \text{ Hz}$
 - Alternatives under consideration may provide enhanced performance and/or flexibility
 - Linac designed to accommodate accelerating gradients in the range $23.6 - 31.5 \text{ MV/m}$ (XFEL – ILC)
 - Final design gradient determined prior to CD-2
- Industrialization role
 - Project X requires 37 $\beta=1$, ILC-like cryomodules
 - Production over a two-to-three-year period represents a significant advance over capabilities anticipated in ~2010; however, the production rate is below that required by ILC
 - ⇒ This activity could represent the initial phase of an industrialization buildup for ILC (in the U.S.).

Project X RD&D Plan


ILC/SRF Joint Development Strategy




- There is a single 1.3 GHz development program at Fermilab, supporting the ILC/GDE program and simultaneously understanding Project X requirements.
 - At an appropriate time (before CD-2) the Project X cryomodule design will be developed.
 - The expectation is that it will be similar, but not identical, to the ILC design (including choice of gradient).
 - The design will be compatible with an identified upgrade path.
 - Creation of facilities capable of fabricating one cryomodule/month remains the responsibility of the SRF infrastructure program.
 - ILCTA-NML is being constructed under the SRF Infrastructure program to support beam testing of a complete rf unit.
 - This configuration supports substantial progress toward ILC (S1 and S2) goals: demonstration of stable high-power operations.
-

Project X RD&D Plan

Relationship to Other Programs: HINS




- The HINS program is developing front end technology beyond the requirements of Project X initial goals:
 - 60 MeV front end @ $27 \text{ mA} \times 1 \text{ msec} \times 10 \text{ Hz}$
 - Demonstrate novel technologies for a high intensity non-relativistic linac
 - Multiple room temperature and sc cavities driven by a single rf source (high power vector modulators)
 - High speed (nsec) beam chopping at 2.5 MeV
 - Establish technical feasibility and cost basis by ~2011



Project X RD&D Plan


HINS Joint Development Strategy



- HINS provides a natural starting point for a Project X upgrade
 - $27 \text{ ma} \times 1 \text{ msec} \times 10 \text{ Hz} = 2 \text{ MW}$ (if accelerated to 8 GeV)
 - Other options: $9 \text{ ma} \times 3 \text{ msec} \times 10 \text{ Hz}$
- Two decisions (prior to CD-2):
 - Do we use HINS as the initial front end or do we utilize a conventional (room temperature) front end?
 - Cost-benefit analysis
 - Can we establish an 8 GeV upgrade path via HINS and if so, how does this impact the 1.3 GHz linac facility design?
- In either case it will be essential to carry the 60 MeV facility through to completion

Project X RD&D Plan

Integrated SRF Plan



	FY08	FY09	FY10	FY11	FY12	FY13
ILC C+CM	CM1	CM2	CM3 (Type IV)		CM4 rf unit sys.tst	
ILC RF Power		MBK	PFN modulator			
SRF Infra.				NML complete		CAF complete (1 CM/month)
HINS				60 MeV beam tests		
Project X		CDR	FE decision Gradient decision baseline docs		rf unit sys.tst	
	CD-0		CD-1	CD-2	CD-3	

Project X RD&D Plan



Relationship to Other Programs: Neutrino Factory

- NF Proton Driver requirements as described by ISS:
- Project X in general will not meet requirements in initial configuration

Proton energy	10±5 GeV	8 GeV
Average beam power	4 MW	360 kW
Pulse rep rate	50 Hz	5 Hz
Proton bunch length (rms)	2±1 nsec	2 nsec*
Number of proton bunches	3 or 5	500 *
Sequential extraction delay	>17 μsec	>17 μsec*
Pulse duration (LHg target)	<40 μsec	>11 μsec*
Pulse duration (solid target)	>20 μsec	>11 μsec*

* Based on accumulation within the Recycler Ring.

Project X RD&D Plan


Neutrino Factory Joint Development Strategy




- Develop upgrade concept for the Project X linac aimed at >2 MW (currently underway)
 - Integrate necessary requirements into the initial (360 kW) design
- Develop a performance specification for a Proton Driver supporting a Neutrino Factory (APC), consistent with Project X concepts.
 - Issues: Average beam power, repetition rate, particles/bunch, bunch intensity
- Develop a conceptual design for the NF Proton Driver based on Project X linac and downstream accumulation/packaging ring(s).
- Coordinate with IDS_NF, NFMCC (, and MCTF)

Project X RD&D Plan

Long Term Vision (R. Palmer)




A Phased Approach



18

Project X RD&D Plan


Collaboration Plan



- Intention is to organize and execute the RD&D Program via a multi-institutional collaboration.
 - Goal is to assign collaborators complete and contained sub-projects, meaning they hold responsibility for design, engineering, cost estimating, and potentially construction if/when Project X proceeds.
 - Project X R&D Collaboration to be established via a Collaboration Memorandum of Understanding (MOU) outlining basic goals of the collaboration, and the means of organizing and executing the work.
 - Goal: Establish RD&D Collaboration by end of FY08
 - It is anticipated that the Project X RD&D Program will be undertaken as a “national project with international participation”. Expectation is that the same structure of MOUs described above would establish the participation of international laboratories.


Project X RD&D Plan

Collaboration Plan



- A draft MOU covering the period through CD-2 is currently circulating for comment among the management of the following potential U.S. collaborators:
 - ANL
 - BNL
 - Cornell
 - LBNL
 - ORNL/SNS
 - MSU
 - TJNAF
 - SLAC
- Expect to hold initial Project X Collaboration Meeting in late summer/early fall

Summary



- Design concept exists for a facility capable of delivering in excess of 2 MW beam power over the energy range 60 – 120 GeV, simultaneous with 8 GeV beam power in the range 100 – 200 kW.
 - Major sub-system performance goals established
 - Design aligned with needs of ILC development
- RD&D plan developed covering the period through CD2 (2011)
 - Integrates effort on Project X, ILC, and HINS
 - Anticipates upgrade to >2 MW at 8 GeV
- Working towards organizing as a national project with international participation.
- Retain good communication with the NFMCC/MCTF to assure Project X is designed to preserve utility in a future muon facility.