



#### **Accelerator Summary**

#### J. Pasternak, Imperial College London / RAL STFC

#### Outline

- Proton driver
- Target
- Front end
- RF in the magnetic field
- Baseline decision in the front end
- Acceleration
- Baseline decision in acceleration
- Decay ring
- Summary



#### Proton Driver Options for the NF

| Base      | Upgrades  | Final<br>Energy |
|-----------|---|-----------------|
| ISIS      | RCS<br>Compressor?  | 9.6 GeV         |
| SPL       | Upgrade Linac<br>Additional GeV of Linac<br>Accumulator<br>Compressor | 5 GeV           |
| Project X | Upgrade Linacs<br>Accumulator<br>Compressor                           | 8 GeV           |



# **Project-X Staging**





#### Additional Rings for the NF

From Gollwitzer -- 9th IDS-NF Meeting







Key Parameters: SC1 <u>IR = 120cm</u> Stored Energy 3GJ

NATIONAL LABORATORY

$$\mathbf{B} = \mathbf{20} \ \mathbf{T}$$

Harold G. Kirk

Arlington, Va. Oct. 2011

6



### **Introduce Discrete Cryo Modules**





Harold G. Kirk Brookhaven National Laboratory

# **Target Module Services**





#### chicane works!

From D. Neuffer

#### Chicane does not reduce transmission by much:

- $0.098 \rightarrow 0.094$  (?) within acceptant
  - ~0.107 without chicane/absorber
- Removes unwanted high energy particles
  - eliminates prepulse from high-energy muons
- Works for both  $\mu$ + and  $\mu$ <sup>-</sup>

#### Integrate into Engineering design?

• Optimize chicane/absorber parameters















Phase Rotation Cell



# Cooling Section CAD Model



( Cooling Cell Section showing 2 modules

Fitting coils between cavities is a problem...

Cell length increased to  $\rightarrow$ 86cm (from 75) + breaks in periodicity

- probably some loss in cooling -
- must study and consider alternatives ...

# New Baseline (NBL) Parameters (1)





From D. Stratakis

Experimental status of RF operation in the magnetic field

## **Cavity Summary**

| Cavity                          | Peak surf. field<br>w/o B Field, w/o<br>Beam (MV/m) | Peak surf. field<br>w/ B Field, w/o<br>Beam (MV/m) | Peak surf. field<br>w/o B Field, w/<br>Beam (MV/m) | Peak surf. field<br>w/ B Field, w/<br>Beam (MV/m) |
|---------------------------------|---|--|--|---|
| 201 MHz                         | 21  | 12   | -  | -   |
| 805 MHz Pillbox<br>(Be buttons) | 40  | 33   | -  | -   |
| All Seasons                     | 25  | 25   | -  | -   |
| HPRF (Cu<br>buttons)            | 60  | 60   | 45*  | 45*   |
|                                 |   | From B. Freemire                                   |  | * DA doped H <sub>2</sub>                         |

#### New Pillbox Cavity Design From B. Freemire

- A new Be wall cavity has been designed; fabrication to begin after review
- Modular
  - ⊢ Easy removal of walls
  - ⊢ Test Cu vs. Be walls
  - Possible to increase cavity length or add other hardware



• New coupler design should eliminate sparking

There are also expected tests of 201 MHz MICE cavity in the magnetic field.

#### Lattices with low magnetic field in the cavities





| E E |  |
|-----|--|
| H   |  |
|     |  |
| H   |  |
|     |  |
|     |  |
|     |  |
|     |  |
|     |  |
|     |  |
|     |  |
|     |  |
|     |  |

| LiH length            | 46 mm                |  |
|-----------------------|----------------------|--|
| RF peak field         | 19 MV/m              |  |
| RF phase              | 30 degrees           |  |
| RF length             | 500 mm               |  |
| Be window thickness   | 0.4 mm               |  |
| Apertures             | 400 mm               |  |
| Coil length           | 1000 mm              |  |
| Coil radial thickness | 100 mm               |  |
| Coil inner radius     | 400 mm               |  |
| Coil current          | 22 A/mm <sup>2</sup> |  |

0.4

0.6

z (m)

0.8

1.0

#### Shielded RF Cooling Channel, C. Rogers

0.0

0.2

### Front End Baseline Decision at this meeting

- There is no current clear understanding, if the problem of RF operation in the magnetic field is seriously limiting the baseline.
- More experimental studies are needed and are planned.
- •Mitigating scenarios proposed to lower the magnetic field has lower performance compared with the baseline.
- •They also do not remove completely the magnetic field from the cavity (the remaining field is lower, but still in the range of 0.3-1 T).



•All changes into the IDS-NF baseline for the RDR will be driven by the feasibility based on engineering study.



For 10 GeV muon acceleration two options have been proposed:

- Option I: using linac and two Recirculating Linear Accelerators (RLAs) it is very similar to the previous baseline part up to 12.6 GeV
- Option II: using linac+RLA+ Nonscaling Fixed Field Alternating Gradient (NS-FFAG) ring NS-FFAG could use the same technology developed for 12.6-25 GeV ring.

Option II was selected at the Nufact'12 due to 5 GeV breaking point, which was favoured as better for an intermediate staging for physics at that time.

#### Linac and RLA – 'in plane' Layout



From A. Bogacz

#### Linac (beam envelope at $2.5\sigma$ )



#### From A. Bogacz

#### Switchyard – Arc 1 and 3



From A. Bogacz

#### Arc 2 and Arc 4



From A. Bogacz

#### **FFAG Designs Comparison**

|                          | 25 GeV machine | 10 GeV machine<br>Scott<br>(preliminary) | 10 GeV machine<br>Jaroslaw<br>(preliminary) |
|--------------------------|----------------|--|---|
| Circumference<br>[m]     | 669            | 434                                      | 369.9                                       |
| Number of RF cavities    | 50             | 36                                       | 26  |
| RF voltage [MV]          | 1196           | 864.8                                    | ~625  |
| Number of<br>turns       | 11.6           | 6.7                                      | 8.5   |
| Number of cells/magnets  | 67/201         | 53/159                                   | 49/147                                      |
| Drift length [m]         | 5              | 3.8                                      | 3.8   |
| Magnetised<br>length [m] | ~263           | ~153.1                                   | ~108.3                                      |



# ns-FFAG Layout with continuous cryomodules





### ns-FFAG cell in a continuous string



FOR THE NEUTRIND FACTORY

# Cryogenic schematic – Continuous string





## Septum magnet – NF ns-FFAG

• Septum design on-going.

 Image below is a work in progress schematic of superconducting 2T extraction septum. 3D design is required to ascertain feasibility.











#### Relative Cost of Systems in EUROnu Report



#### **Status of Costing the Neutrino Factory Accelerator Facility**

#### **Muon Acceleration**

#### Caveats ۲

- The pre-linac solenoid costs have been scaled by length from the cost of the capture solenoids.
- It has been assumed that the RF cavities for the pre-linac and RLAs cost the same as the FFAG RF cavities.
- The aperture for the pre-linac cavities is bigger than the FFAG cavities but the gradient is less. The difference in cost is assumed to be small.
- It has been assumed that the cost of a single-cell cavity (in the pre-linac) is half of a doublecell FFAG cavity.
- It has been assumed that one RF power system can power 4 single-cell cavities.
- It has been assumed that there is no transfer line between the pre-linac and RLA 1.
- The length of the transfer line from RLA 2 to the muon decay ring has been crudely estimated. The cost of the beam line components for the transfer line was based on as-built costs of a higher momentum proton beam transfer line based at CERN from 2002 (and includes an average CHF:GBP exchange rate for 2002 and a UK based inflation factor).

#### Missing items ۲

Aiit

Magnet power supplies and distribution.

#### **9th Plenary Meeting of the IDS-NF 8th October** 2012 Kurup

Page 28



## Costing methodology – to date

- Most costs have been based on similar systems with a touch of "educated estimating". A great deal of research and good communication has enabled us to provide reasonably accurate figures. The NF systems are all unique and require detailed engineering input to improve on the current estimates.
- We have used a linear scaling methodology for varies systems and items. This is reasonably accurate for conventional systems. However, the majority of magnets, RF systems and Cryogenic systems does not scale linearly. This is in need of revision!

# Costing methodology – improvement

- Closer collaboration with companies, laboratories and institutes will provide more accurate costs and includes miscellaneous items previously omitted.
- Apply non linear scaling for systems where figures are not available. This is particularly the case where the manufacturing costs occur. A breakdown of labour and material must be used as a scaling basis.
- Material scaling as a function of length and aperture for instance needs to be refined.
- Where sufficient details are known a 'bottom up' approach needs to be applied with estimates from suppliers.

THE INTERNATIONAL DESIGN STUDY FOR THE NEUTRING FACTORY

## Muon Acceleration Baseline Decision at this meeting

- There is no need for any intermediate energy stage for the NF (no cost advantage due to a different baseline length specification, a different decay ring design and a detector location).
- According to the current cost exercise both options perform very similar.
- •NS-FFAG is a new type of accelerator with some operational risk



• Take Option I (without FFAG and 2 RLAs to 10 GeV) or even modify the old 12.6 GeV option with 2 RLAs.

## But...

- According to the current cost exercise both options perform very similar.
- The error bars are huge, especially as the RLA cost model is scaled from the FFAG one. Are we sure we want to remove a possibility to have options in the system, which is the clear cost driver?

•NS-FFAG is a new type of accelerator with some operational risk The proof of principle has been demonstrated during the EMMA commissioning at Daresbury Lab.

# Consequences ...

• Development of muon FFAG will be stopped within IDS-NF and slowed down in general:

- SC septum integration and feasibility of extraction,
- design of the magnets (mains, SC septum and kickers),
- cryogenics and layout,
- performance in the end-to-end simulations and coupling to RLA.
- further optimisation of cost reduction for muon acceleration.

•It may send a bizarre message that muon acceleration does not need FFAGs (incorrect).



# **Injection Scheme**



- Simultaneous injection of each bunch pair into crossing point
- Delay between consecutive bunch pairs (n + 1/3)\*L
- Kicker rise/fall time is L/(3c) -t<sub>bunch</sub>

D. Kelliher et al.

## Some parameters of the 10 GeV ring

- Circumference 1006 m
- γ<sub>T</sub> 13.927
- Production efficiency 35.8%
- Assumed total momentum spread ±2.5%
- Production straight length 360 m
- Arc length 106.2 m
- $(Q_{H_{,}}Q_{V}) = (9.71, 9.55)$

# Influence of this meeting on the IDS-NF (on the accelerator site)

- This is a very important meeting!
- Strong progress in many areas.
- First official costing results.
- A lot of input from engineering.
- •Important baseline decisions in the front-end and acceleration.
- Setting stage for completing the RDR.



# Thank You